


ASM FS200 Performance Guide

Fully Welded Die Formed Structural Steel Panel Assembly with Lightweight Cementitious Fill

Ultimate Load (lbs)	Concentrated Load (lbs)	Impact Load (lbs)	Rolling Load (lbs) 10 Pass	Rolling Load (lbs) 10,000 Pass
3,900	1,250	175	1,000	800

NOTE: ASM products are tested by a certified United State testing company. Certified test reports in accordance to CISCA test procedures are available upon request.



COMPUTER FLOORS, INC.

19 RICHMOND STREET
CLIFTON, NEW JERSEY 07011
(973) 340-3666 (888) 564-4998
www.computerfloors.us

TITLE:

ASM FS200 HPL PANEL
BOLTED STRINGER SYSTEM
(4' Basket Weave Stringer Sys)

SCALE: NONE